BRUHAT BANGALORE MAHANAGARA PALIKE
YELAHANKA ZONE

Name of work: Estimate for Construction of RCC Drain and Covering slab near Raghavendra Mata at Venkatagiriyappa Layout in ward no 10 (Doddabommasandra), Vidyaranyapura Sub Division.

							Estimate Cost Rs.		**1400000.00**
Sl No	**Description of item**	**Unit**	**No**	**L**	**B**	**D**	**Qty**	**Rate**	**Amount**
1	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. **Page No. 141 / Item No. 19.1 / PWD SR 2014-16**	Cum							
	CC Road		1	60.00	6.00	0.20	72.00		
							72.00	83.16	**5988.00**
	Basic Rate	77.00							
	Area Weightage @8%	6.16							
	Total	**83.16**							
2	KSRB 2.8 : Providing and filling in foundation with granite/trap broken metal 100mm, and down size, with approved sand including had packing, ramming, watering, including cost of all materials and labour with all lead and lift, complete as per specifications. Specification. No. KBS, **Page No. 6 / Item No. 2.15 / PWD SR 2015-16**	Cum							
	For RCC Drain		2	80.00	1.00	0.45	72.00		
							72.00	2174.04	**156531.00**
	Basic Rate	2013.00							
	Area Weightage @8%	161.04							
	Total	**2174.04**							
3	KSRB 4-1.3 : Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2. **No. 12/ Item No. 4.3/ PWD SR 2015-16**	Cum							
	CC Road		1	60.00	6.00	0.15	54.00		
							54.00	5070.60	**273812.00**
	Basic Rate	4695.00							
	Area Weightage @ 8%	375.60							
	Total	**5070.60**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
4	KSRB 4-1.6 : Providing and laying in position plain cement concrete of **mix 1:2:4 with cement @ 240 kgs with 20mm** and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. **No. 12/ Item No. 4.6 / PWD SR 2015-16**	Cum							
	Bottom Concrete CC Drain		2	80.00	1.00	0.10	16.00		
							16.00	5490.72	**87852.00**
	Basic Rate	5084.00							
	Area Weightage @ 8%	406.72							
	Total	**5490.72**							
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for **vertical surface such as walls** at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification NO KBS 4.6.2 **Page No. 15 / Item No. 4.31 / PWD SR 2015-16**	Sqm							
	Side Wall		4	80.00		0.30	96.00		
			2	80.00	0.90		144.00		
			2	80.00		0.15	24.00		
							264.00	306.72	**80974.00**
	Basic Rate	284.00							
	Area Weightage @ 8%	22.72							
	Total	**306.72**							
6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 **TMT Bars FE 500 Page No. 17 / Item No. 4.46.2 / PWD SR 2015-16**	Tonne							
	For RCC Drain @ 60 Kg / Cum		0.06	10.80			**0.65**	69805.80	**45234.00**
	Basic Rate	64635.00							
	Area Weightage @ 8%	5170.80							
	Total	**69805.80**							
7	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. **Page No. 18 / Item No. 4.48 / PWD SR 2015-16**	Cum							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
	CC Road		1	60.00	6.00	0.125	45.00		
	CC Drain Railsing		4	60.00	0.15	0.30	10.80		
							55.80	6332.04	**353328.00**
	Basic Rate	5863.00							
	Area Weightage @ 8%	469.04							
	Total	**6332.04**							
8	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. **174 / Item No. 22.7 / PWD SR 2015-16**	Sqm							
			1	60.00	6.00		360.00		
							360.00	97.20	**34992.00**
	Basic Rate	90.00							
	Area Weightage @ 8%	7.20							
	Total	**97.20**							
9	Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator and HOM of machinery including cost of blade coolant etc including cleaning of groove and providing sand and hot bitumne fillars, and filler metal etc., indluding cost of converyance of all materials, labours, lead and lift charges and all other incidental charges as per drawing and as per specification **Concrete Pavement Page No. 173 / Item No. 22.8.1 / PWD SR 2015-16**	Rmt							
			6	6.00			36.00		
							36.00	124.20	**4471.00**
	Basic Rate	115.00							
	Area Weightage @ 8%	9.20							
	Total	**124.20**							
10	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete7.5 cms thick **Page No. 25 / Item No. 5.31.1/ PWD SR 2015-16**	Sqm							
	For Covering Slab		2	80.00		1.20	192.00		
							192.00	642.60	**123379.00**
	Basic Rate	595.00							
	Area Weightage @ 8%	47.60							
	Total	**642.60**							
11	KSRB 5-9: Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) KBS 5.1.13 **Page No. 24 / Item No. 5.22 / PWD SR 2015-16**	m							
			267	3.60			**960.00**	35.64	**34214.00**
	Basic Rate	33.00							
	Area Weightage @ 8%	2.64							
	Total	**35.64**							
12	KSRB 5-8.2 : Providing two line dressing to granite stone slab / granite stone masonry as per specifications. KBS 5-1.13 **Page No. 24 / Item No. 5.18 / PWD SR 2015-16**	Sqm							
			2	80.00		1.20	192.00		
							192.00	924.48	**177500.00**
	Basic Rate	856.00							
	Area Weightage @ 8%	68.48							
	Total	**924.48**							

Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
13	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. **From 0.00 to 11.90 Km** (PWD SR Rates P No 139)	Cum							
			Qty. Vide Item No. 1				**72.00**	106.34	**7656.00**
	Average weight of earth 1.28 tonne / kg for 11.90 Km = 1.28 TX 11.90Km X 2.0/km= 30.46	30.46							
	Add loading and unloading Charges **It No 17.1 KSRRB M 100-1**	68.00							
		98.46							
	Area Weightage @ 8%	7.88							
	Total	**106.34**							
14	Sub Total								**1385931.00**
15	Third Party Inspection Charges @ 1%								**13859.00**
16	Miscellaneous and other Charges	L/S							**210.00**
								Total	**1400000.00**

(Rupees Fourteen Lakhs Only)

Certificate:

1 The work spot has been inspected and the work is found necessary.
2 This estimate is prepared as per PWD SR of 2015-16.
3 This work included under 2015-16 POW Grants.
4 The provisions were made in this estimate are necessary and adequate.
5 This works come under B.B.M.P. limits.

Assistant Engineer
Ward No. 10

Assistant Executive Engineer
Bruhat Bangalore Mahanagara Palike
Vidyaranyapura Sub Division

Executive Engineer
Bruhat Bangalore Mahanagara Palike
Byatarayanapura Division
5/12/15

Administrative Approval
Accorded For 14,00,000/-
Head of A/C P-1771
CER NO 57 **Dt.** 14.12.2015

TA CE (YNK)

TECHNICAL SANCTION
Accorded For Rs. 14,00,000/-
Head of A/c. P-1771
Div. Ref. No. 246 Date 14.12.15
AE EE(BTP) 15/12